No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Figures	words
					Rs. a. p.	
20	Teakwood windows, 3′×4′ with frames 3″×3¾″ in section with 1″ thick panelled shutters, ¾″ Door iron bars, with iron clamps and iron fittings, etc., complete, including two coats of silicate painting ..	S.ft.	60	2 0 0		
21	Carting and fixing reinforced cement concrete perforated ventilators (supplied departmentally at Bangalore)	,,	200	..		
22	Providing and fixing Mangalore pattern glass roofing tiles	Each	8	5 8 0		

M. A. SRINIVASACHARI,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 14th April 1936.

The attention of the public is invited to the notification, in pages 564-566 of the issue of the *Mysore Gazette*, Part VI, dated 23rd April 1936, inviting tenders for the work of Restoring breached Naravalapalli Dadinavoddu Register No. 783, Bagepalli Taluk.

The last date for receipt of tenders is 9th May 1936.

Abstract Notification dated 25th April 1936.

The attention of the public is invited to the notification, on pages 604-605 of the issue of *Mysore Gazette*, Part VI, dated 30th April 1936, calling for tenders for the work of Restoration of breached Byranahalli Minor Tank, Register No. 35, Narasapur Hobli, Malur Taluk.

The last date fixed for the receipt of tenders in this Office is 2 P.M. on 25th May 1936.

Abstract Notification dated 25th April 1936.

The attention of the public is invited to the notification, on pages 605-606 of the issue of *Mysore Gazette*, Part VI, dated 30th April 1936, calling for tenders for the work of Restoration of Thirumaldevarapalli, Thirumaldevarkere, Minor Tank, Register No. 365 of Bagepalli Taluk.

The last date fixed for the receipt of tenders in this Office is 2 P.M. on 25th May 1936.

Notification dated 28th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, KolarDivision, up to 2 P.M., on 25th May 1936, for Restoring Gollapalli Tank, Register No. 130 of Sidlaghatta Taluk. *An approximate estimate of quantities is given below. These quantities* are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given overleaf showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (Two hundred) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoring Gollapalli Tank, Register No. 130, Sidlaghatta Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 700 has to be shown every month.

Abstract estimate for Restoring Gollapalli Tank, Register No. 130 of Sidlagatta Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	I. BUND R.L. 57.00 TOP WIDTH 4½ FEET, SLOPES 1½ TO 1 AND 2 TO 1.				
1	Jungle clearing with removal of roots, etc. ..	Grade	2 0 0	18	
2	Cutting grips, trenches to bund for the seat of new earth and scraping grass	,,	3 0 0	18	
3	Earthwork to bund with watering and consolidation	C.yds.	0 3 6	7,485	
4	Turfing the slopes	S.yds.	0 0 9	5,943	
5	Removing old stone revetment wherever necessary	L.S.			
6	New stone revetment	C.yds.	1 8 0	343	
7	Providing grade stones cutting figures painting, fixing, etc., complete	Each	1 8 0	18	
8	Do Index stones	,,	0 6 0	18	
9	Do Register No. stone ..	,,	3 0 0	1	
10	Do B.M. stones	,,	2 8 0	2	
11	Do Gauge stone	,,	15 0 0	1	
	Total for bund Rupees ..		..	..	..
	II. SLUICE AT R. L. 45.50.				
1	Repairing the existing sluice, providing plug and with locking arrangements ..	L.S.			
	III. RAISING THE WASTE WEIR BY 3' FROM R.L. 50.00 TO 53.00 AND EXTENDING IT BY 140½'. TOTAL LENGTH 190 FEET AT R.L. 53.00.				
1	Dismantling	L.S.			
2	Earthwork excavating foundations and filling in.	C.yds.	0 3 0	150	
3	Stone jelly concrete in surki mortar	C.ft.	0 4 0	803	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
4	Burnt brick in Surki mortar	C.ft.	0 4 6	1,124	
5	Removing and refixing burnt stone slabs, 6" thick and dressed	S.ft.	0 2 0	113	
6	Burnt stone slabs 6" thick and dressed ..	,,	0 5 0	425	
7	Surki mortar plastering ..	Sqr. yds.	3 8 0	12.40	
8	Removing and refixing old stone apron with new jelly	C.yds.	0 12 0	67	
9	Rough stone work, new for apron ..	,,	1 12 0	56	
10	Joggle joints, 8 ft. C. to C.	Each	0 12 0	25	
	Total for the Weir Rupees				..

N. SUBBA RAO,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 14th April 1936.

Attention of the public is drawn to Notification calling for tenders for 'Opening out a new road from Thavarekere to Bukkapatna in Sira Taluk, in pages 567-568, Part VI of the *Mysore Gazette*, dated 23rd April 1936.

Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 8th May 1936.

An earnest money of Rs. 500 should accompany the tender.

Abstract Notification dated 16th April 1936.

Attention of the public is drawn to notification calling for tenders for 'Opening out a new road from Kallur to Chandrasekharapura and on to Doddagollahalli (Gubbi Taluk Boundary)', in pages 568-569, Part VI of the *Mysore Gazette*, dated 23rd April 1936.

Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 11th May 1936.

Earnest money of Rs. 1,000 should accompany the tender.

Abstract Notification dated 20th April 1936.

The attention of the public is drawn to notification, calling for tenders for the Restoration of breached katte, Kodagikere, Aregujjanahalli, Tumkur Taluk, in pages 607-608, Part VI, in the *Mysore Gazette*, dated 30th April 1936. Tenders will be received by the Executive Engineer, Tumkur Division up to 2 P.M. on 18th May 1936. Earnest money in cash only of Rs. 300 should accompany the tender.

Abstract Notification dated 22nd April 1936.

The attention of the public is drawn to notification, calling for tenders for "Widening the Bund of Kodagihalli Tank on Nademavinpur-Amruthur road" in pages 608-609, Part VI of the *Mysore Gazette*, dated 30th April 1936. Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 18th May 1936. An earnest money in cash of Rs. 200 should accompany the tender.

N. G. KRISHNA IYENGAR,
Executive Engineer.